

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:28

For corners in

Richard B. Blom
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

**SURVEY &
 REMONUMENTATION**

JEC v 5 2000

Register of Deeds Stamp & File Number

Ottawa
 (County)

Located In: Robinson Township Corner Code #I-13

1. Public Land Survey T 7N R 15W I-13
 T ___ R ___ SE corner
 T ___ R ___ Section 34
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P. Englert Jr.
 I, _____, in a field survey on November 11, 19 93,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-13
 L.C.R.C. Liber 6, Page 134, (5-24-91)
 Found 1/2" iron, set C.I.M.
 W. 44.91' to C.I.M. at Olive Twp. corner
 N 65 degrees E 44.84' S. edge stop sign post
 S 10 degrees W 82.33' to 1/2" re-bar
 S 50 degrees W 79.93 to nail in NW corner 4"x4" Post
 N 60 degrees W 80.40' p.k. in NE corner 4"x4" post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13
 Found 4" Harrison Monument in Mon. box
 and accepted as a careful and faithful
 perpetuation of the position of the
 original corner.

W. 44.91' to C.I.M. at Olive cor.
 S 10 degrees W 82.33' to 1/2" rebar
 S 50 degrees W 79.93' nail in NW
 corner 4"x4" Post
 N 60 degrees W 80.40' to PK in NE
 corner 4"x4" Post

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 4" Harrison C.I.M. in monument box
 Centerline top bolt on fire hydrant N 50 degrees E 47.49'
 1/2" re-bar S 10 degrees W 82.33'
 O.C. Remon Tag & Nail in NW, side 4"x4" Post S 65 degrees W 79.84'
 O.C. Remon Tag & Nail in NE. side 4"x4" Post N 63 degrees W 80.41'
 C.I.M. in monument box (Olive corner) West 44.91'

(TAPE)

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date December 3, 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
 RECORDED MAY 14, 1975
 REVISED JAN., 1983