

SURVEY & REMONUMENTATION

JUN 28 1999

RECORDED

98 NOV 11 PM 1:26

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Ray Schultz
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

SECTION

For corners in Robinson Twp.
Ottawa Located In: Corner Code #
 (County)

1. Public Land Survey	T <u>7N</u> R <u>15W</u>	J-1
	T <u> </u> R <u> </u>	North 1/4
	T <u> </u> R <u> </u>	Corner
	T <u> </u> R <u> </u>	Section 2
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on 10/16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1 North 1/4 corner, Section 2, T7N, R15W
 G.L.O. No corner set
 L.C.R.C. Liber 4, Page 6, November, 1979
 Found Cast Iron Monument with Broken Top
 30" Oak WNW 59.55'
 Iron East 33.02'
 NW Corner House No. 14407 SW 64.32'
 S 1/4 Corner Sec 33 (Read 35) West 19.80'

This corner shown on Survey Notes of Exxel Eng. Oct., 1988

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


J-1 Found 4" Cast Iron Monument with Broken Top in $\frac{1}{4}$ N & S Gravel Road about 12" deep on E & W Occupation
 Found 30" Oak No Nail N 79° W 59'±
 Found NW Corner House SW 64'±
 Found S 1/4 corner Section 35 West 19.79'

BA. 043 OTTAWA COUNTY
 PEER APPROVED 10/19/98

This position not established by original government survey. This monument is accepted as the best available evidence of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 North 1/4 corner, Section 2, T7N, R15W
 4" Harrison Cast Iron Monument with Broken Top 0.09' South of Town line
 O.C. Remon Tag & Nail in N side 30" Oak N 79° W 58.99'
 O.C. Remon Tag & Nail in SE side P.Pole S 39° W 101.30'
 O.C. Remon Tag & Nail in SW side 12" Oak S 34° E 107.42'
 O.C. Remon Tag & Nail in NW side 12" Oak N 60° E 53.83'
 S 1/4 corner Section 35, T8N, R15W West 19.79'



\$11.00 CORNER
 Receipt #19293

\$7.00 CORNER
 Receipt #19293

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date 10/17/1998

SURVEY &
REMONUMENTATION

JUN 28 1999

SECTION

