

SURVEY &
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In:	Corner Code ##
	Robinson Twp	
1. Public Land Survey	T <u>7</u> N R <u>15</u> W	J - 3
	T _____ R _____	S. $\frac{1}{4}$ Corner
	T _____ R _____	Section 2
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

RECORDED

95 NOV 29 PM 1:48

Robert A. Kullman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										1			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, Jr., in a field survey on October 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 3 $\frac{1}{4}$ corner common to Sections 2 & 11
Original Corner set May 1832 by Calvin Britain
 $\frac{1}{4}$ Section Post on True Line
Pine 30" N 80° E 22 Links
Beech 10" S 80° W 42 Links

LCRC Liber 11, Page 659
September 8, 1972
Nail in face of 24" Oak NW 68.90'
Nail in face of P.P. SW 74.67'
Nail in face of 10" Apple SE 55.41'
Nail in face of 12" Pine SE 80.39'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 3 $\frac{1}{4}$ corner common to Sections 2 & 11
Found 4" CIM 2" deep
Found 12" Pine ESE 72.40'
Found 30" Oak NNW 74.55'
Found P.P. SW 72.48'

RA. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95
Robert P. Hedewell
YDN

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 3 4" CIM 7'± N. of South edge Gravel Road
Ottawa County Remonumentation tag and nail in NW side of 14" Jack Pine N 47° E 87.67'
Ottawa County Remonumentation tag and nail in N. side 16" Pine S 72° E 71.82'
Ottawa County Remonumentation tag and nail in SE side P.P. S 57° W 72.31'
Ottawa County Remonumentation tag and nail in SW side 36" Oak N 22° W 74.35'

Signed by Carl P. Englert Jr.
Surveyor's Michigan License No. 18987

Date 10/18/1995



J - 3 T 7 N, R 15 W
LCRC Liber 2, Page 801
March 24, 1975
Found Stone and Iron, Set CIM
12" Pine ESE 72.40'
30" Oak WNW 74.55'
P.P. SW 72.48'
CL Stop Sign SE 34.50'

\$ 11.00 CORNER