

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 01 1998

For corners in SECTION

Ottawa
(County)

Located In: Robinson Twp. Corner Code # **K-1**

RECORDED

98 JUL 24 PM-1:45

Dany Schell
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey	T 7 N R 15 W	NW Corner
	T R	Section 1
	T R	
	T 8 N R 15 W	K-13
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	COMMON CORNER TO K-13, T8N, R15W

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Lemke, in a field survey on November 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3	2		1
3													
4	7			8			9			10	11		12
5													
6	18			17			16			15	14		13
7													
8	19			20			21			22	23		24
9													
10	30			29			28			27	26		25
11													
12	31			32			33			34	35		36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 GLO 80.00 Set mile post Pine 30" S 42° E 18 Lks Pine 20" S 25° W 20 Lks May 11 th 1832 By Calvin Britain	L.C.R.C-L2, P 267 John Clapp 6/26/73- Fd. Crockery, Marble, Plow Point, Set Cast Iron Monument (a) 12" Cherry NNW 36.49' (b) Iron W 33.00' (c) Steel bar at CL Cedar Street S 277.51'	Survey Card Holland Engineering C.I.M. J. Kistler & Assoc. 1973 Same as L.C.R.C.-L2, P267
Act 132 Survey John Kistler & Assoc. L1, P 799-6/26/73 Same wit's as shown on LCRC L2-P267	Act 132 Survey John Kistler & Assoc. L1, P 837-7/5/73 Same wit's as shown on LCRC L2-P267	Act 132 Survey Exxel Engineering Co. L4, P 454-10/15/79 Same wit's as shown on LCRC L2-P267

PA. 348 OF OTTAWA COUNTY
DEED APPROVED
4-20-98
Y07

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1- North west corner of section 1. J. Mullett, D.S. in 1837 assumes the corner set by Calvin Britain May 11th 1832 is a corner common to Sections 35 & 36 T.8 N.- R.15W and Sections 1 & 2 T.7 N.- R.15W. After making this assumption he heads East 80.00 chains and intersects the E boundary 38 links north of the temporary post. Based on Mulletts' notes. I accept K-1 as the corner common to both townships. The corner is a 4" cast iron monument with 2 witness's as per LCRC L2-P267, and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Found 4" cast iron monument.
Found Steel bar on section line South 277.51' in centerline of Cedar Street. Same as (c) LCRC L2-P267
Found "T" iron West 33.02' same as (b) LCRC L2-P267
Set nail and 2" washer in E side of 8" Cherry 1.6' above grade N 25° W 40.59'
Found nail and washer in E side of 30" Cherry 2.6' above grade N 15° E 37.25'
Set nail and 2" washer in 12" Apple 0.4' above grade S 85° W 44.45'

99.00 CORNER
Receipt #5013

Signed by *Robert E Lemke*
Surveyor's Michigan License No. 40160 for SDI CONSULTANTS Ltd.



Date 4/20/98

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1998