

DEC 01 1998

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Ottawa
(County)

Located In: Robinson Twp. Corner Code # K-2

RECORDED
98 JUL 24 PM 1:45

Ray S. Seltman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

1. Public Land Survey	T 7 N R 15 W	W. 1/4 Corner
	T R	Section 1
	T R	K-2
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert E. Lemke, in a field survey on November 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2	▲		1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 GLO 40.00 Set 1/2 mile post Pine 30" N 26.5° E 9 Lks Pine 10" S 43° W 27 Lks May 11 th 1832 By Calvin Britain	Survey by E.H. Peck Found Stone (Nov. 1902) Pine 30" S 43° E 19ft Oak Grubb-2" S 7° E 32ft	Witness card 1967 found stone and iron SW to PP 62.05 SE to blazed 12" Oak 28.00 NW to 20" Oak 75.60	L.C.R.C-L2, P 267 John Clapp 6/26/73 Monument Box (a) 20" Oak NW 75.30' (b) P. Pole SW 62.05' (c) St. Sign SE 30.80'
Act 132 Survey John Kistler & Ass. L1, P 799-6/26/73 Same wit's as shown on LCRC L2-P267	Act 132 Survey John Kistler & Ass L1, P 837-7/5/73 Same wit's as shown on LCRC L2-P267 B.	Act 132 Survey Exxel Engineering Co. L4, P 454-10/15/79 Same wit's as shown on LCRC L2-P267	L.C.R.C-L5, P 77 PP Tom Joiner-11/10/83 Fd. Boat spike and iron Set cast iron monument LCRC L2-P267
			SW 62.00' 18" Oak NW 76.75' TP NW 87.74' St. Sign SE 32.10'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2- One-quarter corner common to sections 1 and 2. (b) from L.C.R.C. L5-P77 matches in 1967, '73 and '98. 1902 measure from K-2 to K-3 was 2676.5', Current measure is 2672.91'. Monument is on the centerline of 104th Avenue and is 6.9' south of the centerline of Sleeper Street. The corner is a 3" cast iron monument in monument box and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Found 3" cast iron monument in 0.2 below pavement in monument box on the centerline of 104th Avenue and 6.9' south of the centerline of Sleeper Street
Found. nail and washer(#14091) in NE side of Power Pole S 65° W 62.00' Same as (b) LCRC L2-P267
Set nail and 2" washer in E side of 32" Oak 1.2 above grade N 15° W 76.30'
Set nail and 2" washer in SE side of 12" Twin Box Elder 1.2 above grade N 35° E 92.25'
Set nail and 2" washer in SW side of 22" Spruce 1.2 above grade S 40° E 82.60'

PA. 845 OTTAWA COUNTY

PEER APPROVED

99.00 DOLLARS
RECEIVED #1503

Signed by Robert E. Lemke
Surveyor's Michigan License No. 40160 for SDI CONSULTANTS Ltd.



Date 4/20/98

FORM APPROVED BY MICHIGAN STATE BOARD
OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995