

**SURVEY & REMONUMENTATION**

DEC 16 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located in:	Corner Code #
	Robinson Township	
1. Public Land Survey	T <u>7</u> NR <u>15</u> W	K-4
	T ___ R ___	West $\frac{1}{4}$ corner
	T ___ R ___	Section 11
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

RECORDED

96 NOV 16 AM 11:20

*Calvin Britain*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Englert, in a field survey on 9/12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-4 1/4 corner common to Sections 11 & 12  
G.L.O. 1832 by Calvin Britain

Set 1/2 mile Post  
Elm 10" S46°W 11 Links  
Elm 18" N60°E 49 Links

LCRC Liber 1, Page 659  
October, 1972  
Set Cast Iron Monument  
26" Oak N.E. 107.66'  
16" White Cherry S.E. 70.82'  
N.E. Cor. Hse. S.W. 99.88'  
N. edge of Ditch  
2' E of  $\odot$  104th Ave.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 1/4 corner common to Sections 11 & 12  
Found Cast Iron Monument in Mon. Box 2' E. of centerline of pavement  
Found 26" Oak N.E. 107.66'±  
Found 16" Cherry S.E. 70.82'±  
Found N.E. corner Hse. S.W. 99.88'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 9-16-96

Accepted as a careful and faithful perpetuation of the original position of the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 1/4 corner common to Sections 11 & 12  
4" Harrison Cast Iron Monument in Mon. Box 4" Deep  
O.C. Remon tag & nail in W. side 28" Oak N35°E 108.19'  
O.C. Remon tag & nail in N. side 7" Oak S88°E 42.01'  
O.C. Remon tag & nail in W. side 26" Cherry S26°E 71.49'  
O.C. Remon tag & nail in N. side 13" Elm N. 78°W. 46.68'



Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date 9/16/1996