

**SURVEY & REMONUMENTATION**

APR 24 1995

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:50

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa  
(County)

Located in:  
Robinson Twp.

Corner Code #

- |                                    |                          |                   |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey              | T <u>7N</u> R <u>15W</u> | <u>K-5</u>        |
|                                    | T ___ R ___              | <u>NW Corner</u>  |
|                                    | T ___ R ___              | <u>Section 13</u> |
|                                    | T ___ R ___              | _____             |
| 2. Property Controlling in Section | S ___ T ___ R ___        | _____             |
|                                    | S ___ T ___ R ___        | _____             |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___        | _____             |
|                                    | S ___ T ___ R ___        | _____             |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl P. Englert, in a field survey on November 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-5 corner common to Sections 11,12,13 & 14

Original Gov't corner set May 1832  
by Calvin Britain D.S.

LCRC Liber 1, Page 659 (10/72)

Set Cast Iron Monument

Nail in Face of 8" Tw. Oak SW 128.07

Nail in Face of T.P. SSW 147.05

Nail in Face of P.P. SE 126.91

5' West of E 104th Ave.

Set Corner

Beech 10" S67°E 24 Links

Hemlock 15" N42°W 4 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5 corner common to Sections 11,12,13 & 14

Found broken Harrison Cast Iron Mon. in Mon. Box 6" Deep 5'+/- W. of E Road

Found P.P. SE 126.91' ( No Nail )

Found 16" TW Oak SW 128.07' ( No Nail )

PA. 315 OTTAWA COUNTY

PEER APPROVED 12/12/94

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 corner common to Sections 11,12,13 & 14

4" Harrison Cast Iron Mon. in Mon. Box (broken top)

O.C. Remon. Tag & Nail in N.E. side P.P. S36°E 127.57'


O.C. Remon. Tag & Nail in N.W. side 16" Tw Oak S41°W 128.26'

O.C. Remon. Tag & Nail in N. side P.P. West 29.57'

O.C. Remon. Tag & Nail in W. side P.P. N16°E 270.05'

Signed by Carl P. Englert Jr  
Surveyor's Michigan License No. 18987

Date 12/5/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED MAY 1974