

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:51

For corner **COMMISSION**

D. J. ...
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Ottawa (County) Located In: Robinson Twp. Corner Code # K-8

1. Public Land Survey T 7N R 15W W 1/4 Corner
 T _____ R _____ Section 24
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl P. Englert, in a field survey on November 22, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 K-8 1/4 corner common to Sections 23 & 24
 Original Gov't corner set May, 1832
 by Calvin Britain

Set Post
 Hemlock 10" S31°E 4 Links
 Do 10" N31°W 15 Links

L.C.R.C. Liber 5, Page 94
K-7 - "L" Iron in Mon. Box
 CP/MBT Pole S30°W 66.05'
 22" Maple S60°E 56.70'
 CP/MBT Pole N30°W 76.18'

See Back of Page

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 1/4 corner common to Sections 23 & 24
 Found 3" Harrison Cast Iron Mon. in Mon. Box 1'+/- West of 4" Deep
 Found Twin 12" Maple E.S.E. 46.18'
 Found T.P. (P.P.) S.E. 43.33'
 Found P.P. N.W. 81.12'

OTAWA COUNTY
 PEER APPROVED 12/12/94
Harold D. Newbold

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 1/4 corner common to Sections 23 & 24
 3" Harrison Cast Iron Mon. in Mon. Box
 O.C. Remon Tag & Nail in W. Side P.P. N11°E 171.43'
 O.C. Remon Tag & Nail in S.W. side P.P. N57°W 81.06'
 O.C. Remon Tag & Nail in E. side 45" Beech S20°W 121.30'
 O.C. Remon Tag & Nail in S.W. side P.P. S36°E 43.38'
 O.C. Remon Tag & Nail in S. side 22" Maple S75°E 46.16'



Signed by Carl P. Englert Jr. Date 12/1/94
 Surveyor's Michigan License No. 16967

Liber 3, Page 131

K-8 Found R.R. Spike in Mon. Box
S.E. 43.25' T.P.
N.E. 4" Pine 54.42'
N.W. 81.19' P.P.

1850
2000
2000
2000