

**SURVEY &
REMONUMENTATION**

APR 24 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:50

COMMISSION

For corners in

Phyllis Redman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located in: Robinson Twp.	Corner Code # K-9
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>SW Corner</u> <u>Section 24</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert in a field survey on December 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9 corner common to Sections 23, 24, 25 & 26
Original Gov't corner set May, 1832
by Calvin Britain, D.S.

LCRC Liber 2, Page 169 (5/11)
Set "T" Iron in Mon. Box
£ "X" Pavement N.0.75'
30" Pine N22°W 87.75'
SW cor. Bld. N35°E 99.85'
C.P. Pole S35°E 67.25'

Set Corner
Maple 20" N63°E 20 Links
Hemlock 18" S63°W 34 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 corner common to Sections 23, 24, 25 & 26

Found "T" Iron in Mon. Box 1/5' N. of £ Pavement
Found S.W. Corner Bldg. N35°E 99.85'
Found C.P. Pole S35°E 67.25'
Found 30" Pine N22°W 87.75'

PA. 043 OTTAWA COUNTY
PEER APPROVED 12/12/94
Andrey P. Nebenski

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 corner common to Sections 23, 24, 25 & 26

Set 3/4" x 2' long Iron bar with O.C. Remon. Cap in Mon. Box
O.C. Remon. Tag & Nail in S.E. side 9" Pine S40°W 65.27'
O.C. Remon. Tag & Nail in N.E. side P.P. S35°E 67.15'
O.C. Remon. Tag & Nail in E. side 30" Pine N22°W 87.69'
SW Corner (Brick) Bldg. N35°E 99.40'
£ Pavement SOUTH 1.5' +/-

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 12/11/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
18987 REVISION MAY 24, 1971
REVISION JAN., 1987