

SURVEY & REMONUMENTATION

FEB 27 1998

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 OCT 30 AM 11:00

For corners in **SECTION**

<u>Ottawa</u>	Located In:	Corner Code #	
(County)	Robinson		
	Township		
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>K-10</u>	
	T ___ R ___	<u>W 1/4 corner</u>	
	T ___ R ___	<u>Section 25</u>	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Debra Gant

Register of Deeds
Ottawa County, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on 3/3, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 corner common to Sections 25 and 26	LCRC Liber 1, Pages 559 & 560
G.L.O. 1832 Calvin Britain	K-10 Found Iron
Set 1/2 Mile Post	Set Cast Iron Monument
Maple 18" N41°E 25 links	28" Maple SW 87.29'
Hemlock 7" S30°W 8 links	10" Red Pine SE 78.85'
	Fence Corner NW 34.11'
	Power Pole SE 97.12'
	Street Sign Post SE 43.30' (8-14-72)

See Other Side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 1/4 corner common to Sections 25 and 26	RA. 345 OTTAWA COUNTY
Found 4" Harrison Cast Iron Monument with Broken Top	PEER APPROVED <u>9-15-97</u>
Found P.P. SE 97.12' (Nail in face)	
Found 15" Red Pine SE 78.85'	
Found 36" Maple SW 87± (No Nail)	

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 1/4 corner common to Sections 25 and 26	
4" Harrison Cast Iron Monument with Broken Top	
O.C. Remon Tag & Nail in NW Side 36" Maple	S52°W 87.56'
O.C. Remon Tag & Nail in SW Side 15" Red Pine	S30°E 79.05'
O.C. Remon Tag & Nail in S Side Power Pole	S75°E 97.78'
O.C. Remon Tag & Nail in W Side 8" Oak	N25°E 98.46'
Gravel Road is East 8 feet ±	



\$ 2.00 PHOTO

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 9/15/1997

Robinson Township, Section 26, Town 7 North, Range 15 West
Liber 3, Page 279

K-10

12" Red Pine S20°E 78.88'

Power Pole S80°E 97.23'

Triple 8" Maple N30°E 69.32' (7-26-78)

SURVEY &
REMONUMENTATION

FEB 27 1998

SECTION