

# SURVEY & REMONUMENTATION

APR 24 1995

## OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:51

For corners **COMMISSION**

*Phyllis Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In: Robinson Twp.	Corner Code -# L-7
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>S 1/4 Corner</u> <u>Section 13</u>
2. Property Controlling in Section	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl P. Englert, in a field survey on December 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 L-7 1/4 corner common to Sections 13 & 14 LCRC Liber 4, Page 61 (4/25/80)  
 Original Gov't corner set May, 1832 L-7 Set Cast Iron Monument  
 by Calvin Britain, D.S. Ties taken"  
 ♂ 40" Maple SW 31.75'  
 ♂ 8" Aspen SE 40.87'  
 ♂ 24" Red Oak NE 37.00'  
 ♂ Trail to The South West 17'+/-  
 ♂ Bass Creek West 60'+/-

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 L-7 1/4 corner common to Sections 13 & 14

Found 4" Harrison CIM 1" deep 4'+/- South of Road E  
 Found 36" Maple SW 31.75'  
 Found 8" Aspen SE 40.87'  
 Found 24" Red Oak NE 37.00'


P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/12/94

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 L-7 1/4 corner common to Sections 13 & 14

4" Harrison Cast Iron Monument  
 O.C. Remon. Tag & Nail in S. side 24" W. Pine N77°E 125.68'  
 O.C. Remon. Tag & Nail in S.E. side 28" Oak N36°E 36.48'  
 O.C. Remon. Tag & Nail in S.E. side 12" Aspen S56°E 40.79'  
 O.C. Remon. Tag & Nail in W. side 36" Maple S18°W 31.41'  
 O.C. Remon. Tag & Nail in E. side 18" Maple S38°W 67.73'

Signed by Carl P. Englert Jr Date 12/7/94  
 Surveyor's Michigan License No. 18987



LCRC Liber 2, Page 169 (5/11/73)

L-7 - "T" Iron

20" Maple	N40°E	36.57'
16" Maple	N60°E	56.30'
36" Maple	S16°W	31.20'
10" Wd Cherry	S50°W	45.50'

2006 #  
2007 #  
2008 #  
2009 #  
2010 #  
2011 #  
2012 #  
2013 #  
2014 #  
2015 #  
2016 #  
2017 #  
2018 #  
2019 #  
2020 #  
2021 #  
2022 #  
2023 #  
2024 #  
2025 #  
2026 #  
2027 #  
2028 #  
2029 #  
2030 #