

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

99 DEC -2 PM 1:13

SECTION

For corners in

OTTAWA
(County)

Located in: ROBINSON
(Township)

Corner Code #L-11

- 1. Public Land Survey T 7N R15W N¼ of Sec.36
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Ray Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert E. Lemke, surveyor, in a field survey on September 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, reestablished, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			11
5													
6	18			17			16			15			14
7													
8	19			20			21			22			23
9													
10	30			29			28			27			26
11													25
12	31			32			33			34			35
13													36

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

11/15/99
RD7

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 FOUND ANGLE IRON 4" BELOW SURFACE OF GROUND
FROM L.C.R.C. LIBER 1 PAGE 589
IRON N 33.00' M=32.63'
C/L PIERCE ST S 16' M=17.5'



SURVEY RECORDED . LIBER 7 PAGE 513

P.K. NAIL IN S. SIDE P. POLE WNW. 97.06' M=97.05'
SE. COR. BRICK HOUSE NW. 141.69' M=141.61'

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 SET 36" BY .75" STANDARD REMON MARKER WITH CAP

SET NAIL AND OTTAWA COUNTY REMON. TAG IN S. SIDE OF TELEPHONE POLE	N 75°W	97.03'(1.0')	ABOVE GRADE
SET NAIL AND OTTAWA COUNTY REMON. TAG IN N.W. SIDE OF 11" OAK	N 45°E	32.60'(2')	ABOVE GRADE
SET NAIL AND OTTAWA COUNTY REMON. TAG IN WEST SIDE OF PWR POLE	S 00°W	38.04'(1.5')	ABOVE GRADE
FOUND ANGLE IRON	NORTH	32.63'	
SE. COR. BRICK HOUSE	N40°W.	141.61'	

Signed by *Robert E. Lemke*
For SDI CONSULTANTS, LTD

Date *11-15-1999*

Surveyor's Michigan License No. 40160

SEE BACK

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
JAN. 28, 1971 REVISED MAY 14, 1976
REVISED JAN., 1983
REVISED OCT., 1995

\$11.00 CORNER
Receipt #64945

FEB 24 2000

OTTAWA COUNTY
ROBINSON TOWNSHIP
TOWN 7 NORTH, RANGE 15 WEST

SECTION

L-11

A. Description of original monument and accessories and/or subsequent restoration

-G.L.O.

39.22 ¼ SEC POST ON TRUE LINE
HEMK 12 S61E 25
DO 12 N61W 18
May 1832; C. Britain

-JOHN CLAPP, RECORDED L.C.R.C. LIBER 1 PAGE 589 DATED: 07-14-1972
FOUND ANGLE IRON

POWER POLE NW 57.47'
36" ASPEN S 40.05'
TEL. POLE NE 96.86'
IRON N 33.00'
C/L PIERCE ST S 16'

-MAURICE ROSEMA, RECORDED BOUNDARY SURVEY LIBER 7 PAGE 513 DATED: 5-24-1991
ANGLE IRON

P.K. NAIL IN S. SIDE P. POLE WNW. 97.06'
NAIL IN E. SIDE T. POLE S. 43.61'
SE. COR. BRICK HOUSE NW. 141.69'
CENTERLINE E.-W. GRAVEL ROAD S. 16'

(ROSEMA SHOWS SAME WITNESSES AS RECORDED LIBER 7, PAGE 513 ON THE FOLLOWING RECORDED
BOUNDARY SURVEYS)

LIBER 7 PAGE 512 DATED: 5-24-1991
LIBER 9 PAGE 66 DATED: 5-24-1991