

SURVEY & REMONUMENTATION

DEC 01 1998

SECTION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>OTTAWA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	M-4 (E 1/4 corner Section 12) Robinson Twp.
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

RECORDED
98 SEP 29 PM 1:56

Randy DeBolt
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugteveen, in a field survey on May 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-4 set by G.L.O. May 1832 Calvin Britain Set Post 14" ELM N4°W 47 links 6" Tamarack S48°W 38 links	M-4 Liber 5, Page 249 July 1985 Joiner Set Cast Iron Monument Power Pole NE 19.63 (Believed to be typo) 7" Maple NW 40.31 9" Maple SW 42.53 Allendale corner S 13.84'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 found Cast Iron Monument

Nail & Tag West side Power Pole Az 55° 119.65' Nail N. Side 8" Maple Az 294° 40.20' Nail S side 12" Maple Az 235° 42.50' Cast iron Monument South 13.86'	Accepted Cast Iron Monument as a careful and faithful perpetuation of the position of the original corner.
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

M-4 Cast Iron Monument

Nail and Ottawa County Remon Tag on W side Power Pole Az 55° 119.65'
Nail and Ottawa County Remon Tag on N side 10" Maple Az 275° 35.30'
Nail and Ottawa County Remon Tag on S side 12" Maple Az 235° 42.50'
Cast Iron Monument at Allendale Twp corner Az 180° 13.86'
Top of Bank overlooking Lowland Az 270° 15' +/-

Randy DeBolt
6/1/98

STATE OF MICHIGAN
RANDALL VUGTEVEEN
NO. 28429
LICENSED LAND SURVEYOR

Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date July 23, 1998