

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:50

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In: Robinson Twp.	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>M-6</u>
	T _____ R _____	<u>E 1/4 Corner</u>
	T _____ R _____	<u>Section 13</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl P. Englert, in a field survey on August 04, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-6 East 1/4 corner Section 13  
Original Gov't corner set May, 1832  
By Calvin Britain, D.S.

Set 1/2 Mile Post  
Beech 10" S53°W 20 Links  
Hemlock 9" N19°W 9 Links

LCRC Liber 4, Page 39 (1/15/80)  
Set CIM in place of iron pipe  
Iron Stake W. 63.20'  
Iron Stake N 38.35'  
W. 1/4 Cor. 18-7-14 S. 53.80'  
12" Quad. Maple E. 43.12'  
P.P. N.E. 51.12'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 East 1/4 corner Section 13

Found 4" Harrison CIM with Broken Top  
Found P.P. N.E. 51.12'  
Found W. 1/4 Cor. Sec. 18-7-14 S. 53.79'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

*Handwritten signature: Wesley P. Hebert*

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 East 1/4 corner Section 13

4" Harrison Cast Iron Monument with Broken Top  
O.C. Remon. Tag & Nail in N. side 14" Maple  
O.C. Remon. Tag & Nail in W. side 38" Oak  
O.C. Remon. Tag & Nail in S. side 12" Ash  
O.C. Remon. Tag & Nail in E. side 6" Maple  
O.C. Remon. Tag & Nail in S.E. side P.P.  
CIM at T7N, R14W corner

S76°E 44.36'  
S 90°E 33.53'  
S79°W 88.83'  
N27°W 34.12'  
N25°E 51.15'  
South 53.79'

Signed by Carl P. Englert  
Surveyor's Michigan License No. 18987

Date 12/7/94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS

