

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:51

For corners in **COMMISSION**

Daphne Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
	Robinson Twp.	
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	<u>M-8</u>
	T _____ R _____	<u>E. 1/4 Corner</u>
	T _____ R _____	<u>Section 24</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl P. Englert, in a field survey on December 05, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-8 East 1/4 corner Section 24
Original Gov't corner set May, 1832 by Calvin Britain D.S. LCRC Liber 5, Page 373 (6/21/89)
M-8
Set CIM
Set 1/2 Mile Post W 1/4 Corner of 19-7-14 S 52.65'
Hemlock 10" S46°W 32 Links Nail in E face 18" Birch SSE 37.89'
Hemlock 16" N 40°W 15 Links Nail in S face 10" Birch W 22.24'
Nail in SE face 16" Oak N 25.76'
Nail in W face 40" Twin NE 32.24'

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 East 1/4 corner Section 24
Found 4" Harrison CIM 2" above ground
Found Nail in E. face 18" Birch SSE 37.89'
Found Nail in S. face 10" Birch WEST 22.24'
Found 16" Oak NORTH 26.00'+/-
Found 40" Twin Oak NE 32.00'+/-

Accepted as a careful and faithful perpetuation of the original position of the corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 East 1/4 corner Section 24

Harold P. Nedeweld

4" Harrison Cast Iron Monument
O.C. Remon. Tag & Nail in W. side 40" Twin Oak N20°W 30.85'
O.C. Remon. Tag & Nail in E. side 20" Yel. Birch S12°E 37.93'
O.C. Remon. Tag & Nail in S.W. side 24" Oak N40°W 36.71'
O.C. Remon. Tag & Nail in S. side 12" W. Birch WEST 22.05'

Signed by Carl P. Englert Jr
Surveyor's Michigan License No. 18987

Date 12/7/94



LCRC Liber 6, Page 41 (8/7/81)

M-8= Set 1" Pipe with cap midway and on line
North 14" Oak 25.94'
N.N.E. 34" Oak 32.00'
S.S.E. 18" Birch 38.28'
Allendale Corner South 52.15'

2007 # 2000
2007 # 2000
2007 # 2000
2007 # 2000