

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
94 DEC -8 PM 12:35

Edyellie Kallman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In: Robinson Twp.	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>15W</u>	M-9
	T _____ R _____	SE Corner
	T _____ R _____	Section 24
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl P. Englert, in a field survey on March 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M-9 Corner Common to Sections 24 & 25
Original gov't corner set May, 1832
by Cavlin Britain D.S.

Set corner to Sections 24 & 25
Lynn 12" S40°W 29 Links
Elm 20" N33°W 33 Links

M-9 L.C.R.C. Liber 4, Page 63 (5/15/80)
Found Angle Iron & 1 1/4" Pipe, Set CIM
Centerline Tel. Pole N.W. 40.80'
Centerline P.P. N.N.W. 59.07'
Centerline St. Sing S.W. 5.4'
N. Edge Asphalt Pavement S. 16.4'

(See Back of Page)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-9 corner common to Sections 24 & 25
Found 4" Harrison Cast Iron Monument
Found Stub of Tel. Pole N.W. 40.8'
Found P.P. N.N.W. 59.07'
Bldg's are there but have been altered.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Andrew D. McDowell

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-9 corner common to Sections 24 & 25
4" Harrison Cast Iron Monument Next to W. Leg of Sign
North edge of pavement South 10.3'
O.C. Remon. Tag & Nail in W. Side Guy P. N.10°E 23.50'
Angel Iron in Monument Box South 52.86'
O.C. Remon. Tag & Nail in S.E. Side 18" Spruce S.30°W 109.78'
O.C. Remon. Tag & Nail in N.W. Side 14" Box Elder N.75°E 61.74'
O.C. Remon. Tag & Nail in E. Side 10" Sycamore N.40°W 69.09'

Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 11/21/94



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

L.C.R.C. Liber 2, Page 171 (6/5/93)

Found Angle Iron

Angle Iron S.W. Corner Section 19-7-14 S. 52.80'

S.W. Corner Bldg. N.60°E 119.40'

S.E. Corner Bldg. N.35°W 160.20'

N.W. Corner Bldg. S.20°E 99.90'

Centerline Pavement South 26.2'

170 #
150 #
2.00 #
1555 #
2000 #
2000 #
2000 #