

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> (County)	Located In: Robinson Township	Corner Code # M-10
1. Public Land Survey	T <u>7</u> N R <u>15</u> W	East $\frac{1}{4}$ corner Section 25
	T ___ R ___	
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

RECORDED
96 NOV 14 AM 11:21
Regina Johnson
REGISTER OF DEEDS
OTTAWA COUNTY MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, in a field survey on 9/9, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-10 E 1/4 Corner Section 25	LCRC Liber 1, Page 525 July 1972
G.L.O. May 1832 by Calvin Britain	Found Iron Pipe
Set 1/2 mile Post	16" Elm N.W. 49.00'
Hemlock 15" S65°W 5 Links	"T." Iron E. 22.30'
Sugar 10" N15°W 47 Links	Te1 Pole S.W. 44.40'
See other side	St. Sign N80°E 23.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


M-10 E 1/4 Corner Section 25
Found Cast Iron Monument in Monument Box
Found P.P. S.E. 41.42'
Found P.P. S.W. 45.08'
Found Allendale corner South 29.31'

RA. 345 OTTAWA COUNTY
PEER APPROVED 9-16-96
[Signature]

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 E 1/4 Corner Section 25
4" Cast Iron Monument in Monument Box in centerline of Pavement
O.C. Remon tag & nail in W. Side P.P. N85°E 231.56'
O.C. Remon tag & nail in N.W. Side P.P. S51°W 45.30'
O.C. Remon tag & nail in S.W. Side P.P. S43°E 41.94'
Centerline of 4" Maple N40°W 74.22'
Allendale corner South 29.31'



Signed by Carl P. Englert
Surveyor's Michigan License No. 18987

Date 9/16/1996

SURVEY &
REMONUMENTATION

DEC 1 8 1996

COMMISSION

M-10 E 1/4 corner Section 25 T7N R15W
LCRC Liber 4, Page 80, July 1980
Found 3/4" Pipe, Set Cast Iron Monument
P.P. S.E. 41.42'
P.P. S.W. 45.08'
N.W. cor. of Garage S.E. 83.84'
Allendale Corner South 29.31'