

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>16W</u>	E-3, SW corner Section 4 Grand Haven Twp
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 29 PM 1:40

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, THOMAS E. JOINER in a field survey on 11-7- 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3			●									
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

05-24-1832	Liber 1, Page 61 09-20-71
Post Set By Calvin Britain, D.S.	Found 1" Angle Iron Bent Over Limestone
N 75° W 39 14" Sugar Maple	NE 5.65 10" Beech
N 25° E 49 12" Sugar Maple	S 4.90 10" Beech
	SW 24.75 8" Maple
	NW 16.43 20" Oak
	N 32.82 Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful
perpetuation of the position of the original corner.

Liber 1, Page 61 09-20-71
SW 24.75 8" Maple
NW 16.43 20" Oak
N 32.82 Iron Pipe

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Madison P. Redwood
MDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in E side 18" Maple	AZ 197°	9.85
O.C. Remon Tag & Nail in S side Twin 15" Oak	AZ 95°	29.96
O.C. Remon Tag & Nail in SW side 22" Oak	AZ 318°	17.67
O.C. Remon Tag & Nail in W side 12" Maple	AZ 220°	44.33



Signed by Thomas E. Joiner Date 11-16-95
Surveyor's Michigan License No. 18435