

DEC 01 1998

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 7 N R 16 W	E-8
	T R	
	T R	
	T R	West 1/4 corner
2. Property Controlling in Section	S T R	Section 21
	S T R	Grand Haven Twp
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
98 JUL 24 PM 1:45

Harry Schellton
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Steve Lampen, in a field survey on May 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-8 GLO - Britain - 1832 South between Sec 20 & 21 40.00 set 1/2 mile post Beech 10 N 15 E 10 DO 12 S 15 W 12	E-8 is shown on the Plats of Hubbell Acres - 1951 Juniper Hills - 1965	LCRC - L2 P233 - Clapp E-8 is shown as F-8 Iron in Lakeshore Ave 15" Maple (E. face) NW cor conc blk cottage SE 93.81
--	---	---

LCRC - L4 P50 - Kirk Van Order
Found conc monument, set cast iron monument
16" Maple W 15.55
SW cor block cottage SE 91.61
NW cor block cottage SE 93.88
Centerline wd fence cor post NW 0.50
NE corner house NW 131.43

PA. 345 OTTAWA COUNTY
DEED APPROVED 6-15-98

YON

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8
Found cast iron monument SW corner block cottage SE 91.61

The position of the cast iron monument fits the monumentation of Hubbell Acres Subdivision and Juniper Hills Subdivision

The position of the cast iron monument is accepted as a careful and faithful perpetuation of the position of the original corner



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8

Cast iron monument	Azimuth = compass		
Remonumentation tag in SW side	4" Maple	305°	6.49
Centerline	4" Pine	335°	9.15
SW corner concrete block house		139°	91.52
NW corner concrete block house		129°	86.86

Signed by Steven Lampen Date JULY 20, 1998

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1993

REVISOR MAY 14, 1993
REVISOR JAN. 28, 1993
ADAPTED FOR WORD PROCESSING MARCH, 1993

\$9.00 CORNER
Receipt # 2003