

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:40

For corners in

OTTAWA _____
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-----------------------------|
| 1. Public Land Survey | T <u>7N</u> R <u>16W</u> | F-5, S $\frac{1}{2}$ Corner |
| | T _____ R _____ | Section 9 |
| | T _____ R _____ | Grand Haven Twp. |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Edyella Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS E. JOINER in a field survey on 10-26- 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 05-24-1832 Liber 1, Pg. 373, 05-11-72
 Post set by Calvin Britain, D.S. Set cast iron monument
 N17°E 52 18" Beech NW 46.24 Nail in face of 18" Maple
 S32°E 40 15" Sugar NE 50.68 Nail in face of 10" Maple
 SW 67.65 Nail in face of Power Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 1, Pg. 373, 05-11-72
 NW 46.24 Nail in face of 18" Maple
 NE 50.68 Nail in face of 10" Maple
 SW 67.75 Nail in face of power pole

Harold P. Hedewald

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument in Monument Box

O.C. Remon. Tag & Nail in SE side 24" Maple	Az. 35° 50.83
NW cor. 6' X 3' conc. Veterans Memorial Monument	Az. 130° 119.98
O.C. Remon Tag & Nail in W side 22" White Pine	Az. 175° 100.54
O.C. Remon Tag & Nail in SW side 23" Maple	Az. 326° 47.05

Signed by Thomas E. Joiner Date 11-28-94
 Surveyor's Michigan License No. 18435