

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:40

Phyllis Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in
Ottawa
 (County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|--------------------------|--|
| 1. Public Land Survey | T <u>7N</u> R <u>16W</u> | F-7, S $\frac{1}{2}$ cor. Section 16 Grand Haven Twp |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

**SURVEY &
 REMONUMENTATION**

JEC 05 2000

SECTION _____
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

I, THOMAS E. JOINER, in a field survey on 10-26-94, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | | |
|----------------------------------|---------------------------|----------------------------|
| 05-24-1832 | Liber 4, Pg. 15, 12-11-79 | Liber 1, Pg. 669, 10-13-72 |
| Post set by Calvin Britain, D.S. | Found #80 Penny Spike | Found Iron |
| N 43° W 32 10" Beech | South 24.95 24" Maple | South 24.95 24" Maple |
| S 33° E 12 8" Beech | SW 30.90 36" Maple | SW 30.90 36" Maple |
| Liber 1, Pg. 633, 09-18-72 | NE 33.22 18" Maple | NE 33.22 18" Maple |
| Found 3/4" Spike | SE 45.28 10" Maple | SE 45.28 10" Maple |
| South 24.97 22" Maple | North 44.89 8" Maple | North 44.89 8" Ash |
| SW 30.91 36" Maple | North 33.00 Iron | North 33.00 Iron |
| NE 33.22 18" Maple | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

| | | |
|---------------------------|---------------------------|----------------------------|
| Liber 4, Pg. 15, 12-11-79 | Liber 1, Pg. 669 10-13-72 | Liber 1, Pg. 633, 09-18-72 |
| NE 33.22 18" Maple | NE 33.22 18" Maple | NE 33.22 18" Maple |
| North 44.89 8" Ash | North 44.89 8" Ash | |
| North 33.00 Iron | North 33.00 Iron | |
| SE 45.28 10" Maple | SE 45.28 10" Maple | |

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument in Monument Box

| | | |
|--|-----------|-------|
| O.C. Remon. Tag & Nail in W side 14" Ash | Az. North | 45.26 |
| O.C. Remon. Tag & Nail in W side 15" Maple | Az. 26° | 34.07 |
| O.C. Remon. Tag & Nail in W side 12" Maple | Az. 130° | 45.85 |
| O.C. Remon. Tag & Nail in E side 40" Maple | Az. 218° | 32.23 |

Signed by Thomas E. Joiner Date 11-28-94
 Surveyor's Michigan License No. 18435