

REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>16W</u>	G-2, E $\frac{1}{4}$ corner
	T _____ R _____	Section 4
	T _____ R _____	Grand Haven Twp
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 29 PM 1:39

Richard Ballman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Thomas E. Joiner, in a field survey on 11/9, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

05-22-1832	Liber 5, Page 107	06-14-84
Post Set By Calvin Britain, D.S.	Found Steel Bar	
S 10° W 22 18" Hemlock	NE 47.11 G Hydrant	
N 30° E 20 6" Beech	SW 65.11 18" Pine	
	WSW 18.1 Street Sign	
	W 62.38 40" Oak	
	WNW 26.02 13" Oak	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Steel Bar and accepted as a careful and faithful perpetuation of the position of the original corner.
 Set Cast Iron Monument

Liber 5, Page 107
 NE 47.11 G Hydrant
 SW 65.11 18" Pine
 WSW 18.1 Street Sign
 W 62.38 40" Oak
 WNW 26.02 13" Oak

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11/20/95

Madison D. Newell
 GDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument		
G _L Top Operating Bolt on Hydrant	AZ 60°	47.02
O.C. Remon Tag & Nail in S side 42" Oak	AZ 270°	62.54
O.C. Remon Tag & Nail in SE side 16" White Pine	AZ 240°	34.10
O.C. Remon Tag & Nail in NW side 20" Oak	AZ 35°	79.70



Signed by Thomas E. Joiner Date 11-16-95

Surveyor's Michigan License No. 18435