

# SURVEY & REMONUMENTATION

FEB 27 1998

## Ottawa County Remonumentation LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **SECTION**

Ottawa <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>16W</u>	<u>G-10</u>
	T _____ R _____	<u>W<sup>1</sup> corner</u>
	T _____ R _____	<u>Section 27</u>
	T _____ R _____	<u>Grand Haven Twp</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**RECORDED**  
97 DEC -8 AM 11:28

*Gay Robertson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, THOMAS E. JOINER, in a field survey on 11-22-, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

G-10 Calvin Britain D.S. (1832)	Liber 1, Page 801 11-7-72	Liber 4, Page 188 5-7-81
Set 1/2 mile post	Found 1" pipe in monument box	Found iron pipe set cast
12" Beech N61°W 15 links	street sign SE 47.71	iron monument in box
10" Maple S62°E 5 links	36" Oak NW 39.09	37" Oak NW 41.01'
	10" Maple NE 46.78	14" Maple NE 47.29'
	32" White Pine NE 82.82	19" Oak WSW 26.88'
	14" Oak WSW 26.38	5" Poplar SE 69.22'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-10 Found broken cast iron monument in box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 1, Page 801	Liber 4, Page 188
Street sign SE 47.71'	37" Oak NW 41.01'
36" oak NW 39.09'	14" Maple NE 47.29'
32" White Pine NE 82.82'	

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12-1-97



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-10 Found broken cast iron monument in box			
Ottawa County Remon Tag & nail in NE side 10" Aspen	AZ 150°	Dist 52.46	\$ 9.00 CORNER \$ 1.00 PHOTO
Ottawa County Remon Tag & nail in S side 21" White Pine	AZ 60°	Dist 78.56	
Ottawa County Remon Tag & nail in S side 37" Oak	AZ 330°	Dist 40.82	
Ottawa County Remon Tag & nail in W side Twin 15" Oak	AZ 210°	Dist 63.65	

G-10 on center line paved road to North  
on center line gravel road to South  
on center line gravel road to East

Signed by Thomas E. Joiner Date 12-1-97  
Surveyor's Michigan License No. 18435