

1993

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 16 PM 1:00

COMMISSION

For corners in

*Phyllis Kellman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in	Located In:	Corner Code #
<u>Ottawa</u> (County)		
1. Public Land Survey	T <u>7N</u> R <u>16N</u>	I-12, W $\frac{1}{4}$ Corner Section 35
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, THOMAS E. JOINER, in a field survey on 10-28-, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Cast Iron Monument Liber 1, Pg. 119  
Midway and on line between Section Corners

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found cast iron monument and accepted as a careful and faithful perpetuation of the position of the original corner.

10" Red Pine N 65° W 59.00  
12" White Pine S 70° W 49.76



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon tag & nail North Side 12" Cherry S. 66° W. 50.02  
O.C. Remon tag & nail South Side 10" Red Pine N. 83° W. 66.00  
O.C. Remon tag & nail East Side 10" Red Pine N. 46° W. 59.10  
O.C. Remon tag & nail West Side 7" Oak S. 17° W. 86.22

Signed by Thomas E. Joiner Date 11-19-93  
Surveyor's Michigan License No. 18435