

SURVEY & REMONUMENTATION

OCT 07 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>7</u> R <u>16</u>	<u>K-1, NE corner</u> <u>Section 2</u> <u>Grand Haven Twp</u>
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

RECORDED

96 AUG 26 PM 2: 01

P. Lyndell Coleman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Thomas E. Joiner, in a field survey on January 24, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1832	Liber 4, Page 298
Post Set By Calvin Britain, D.S.	Found Iron Pipe, Set Cast Iron Monument
S 16° E 28 6" White Oak	16" Oak S 19.83
S 34° W 22 8: White Oak	30" Oak E 19.40
	10" Pine NE 13.45
	25" Oak N 19.94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 4, Page 298
 Cast Iron Monument

16" Oak S 19.83
 30" Oak E 19.40
 10" Pine NE 13.45
 25" Oak N 19.94

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 8-20-96

Robert P. McDowell



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument	
Ottawa County Remon tag and nail in NW side 21" Oak	AZ 225° 8.14
Ottawa County Remon tag and nail in N side 30" Oak	AZ 95° 19.29
Ottawa County Remon tag and nail in E side 24" Oak	AZ 8° 20.00
Ottawa County Remon tag and nail in NE side 28" White Pine	AZ 65° 41.75

Signed by Thomas E. Joiner Date 2-16-96
 Surveyor's Michigan License No. 18435