

SURVEY &  
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 16W	K-5, SE corner Section 11 Grand Haven Twp
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:39

*Edythe R. Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER, in a field survey on 11-2-, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

05-17-1832	Liber 1, Page 5 05-03-71
Post Set By Calvin Britain, D.S.	Found Iron Pipe
N 71°E 6 6" Beech	Set Cast Iron Monument
N 70°W 25 18" Beech	NE 42.50 $\phi$ Street Sign
	SE 70.00 Power Pole
	SW 59.35 Telephone Pole
	NW 67.75 10" Cherry

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 1, Page 5 05-03-71  
NW 67.75 10" Cherry  
SE 70.00 Power Pole


P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95

*Robert D. Newell*  
RDN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in E side	15" Maple	AZ 25°	94.21
O.C. Remon Tag & Nail in W side	18" Maple	AZ 203°	79.91
O.C. Remon Tag & Nail in W side	25" Maple	AZ 165°	88.35
$\phi$ Top Operating Bolt Hydrant		AZ 316°	52.41



Signed by Thomas E. Joiner Date 11-16-95  
Surveyor's Michigan License No. 18435