

OTTAWA COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:41

For corners in
 OTTAWA

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>16W</u>	K-7, SW Corner
	T _____ R _____	Section <u>13</u>
	T _____ R _____	Grand Haven Twp.
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard Calmon
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

SURVEY &
 REMONUMENTATION

DEC 05 2000

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER in a field survey on 10-28-, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

05-17-1832	Liber 2, Pg. 649, 10-09-74	Liber 2, Pg. 281, 08-07-73
Post set by Calvin Britain, D.S.	Found cast iron monument	Found iron in monument box
S24°E 12 24" Hemlock	NE 67.16 30" Ash	SE 41.70 Street Sign
W. 7 6" Hemlock	SE 64.77 20" Maple	NW 67.40 12" Pine
	SW 95.76 15" Pine	SW 64.80 24" Oak
	NW 61.87 14" Pine	Liber 1, Pg. 569, 08-21-72
		Found iron pipe
		NE 67.05 28" Ash
		SE 36.50 E Street Sign
		SW 47.65 10" Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: NW 59.96 8" Pine
 Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 2, Pg. 649, 10-09-74	Liber 2, Pg. 81, 08-07-73	Liber 1, Pg. 569, 08-21-72
NE 67.16 30" Ash	NW 67.40 12" Pine	NE 67.05 28" Ash
SE 64.77 20" Maple		SE 36.50 C _L Street Sign
SW 95.76 15" Pine		
NW 61.87 14" Pine		

PA. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon. Tag & Nail in W side 36" Ash	Az. 30°	68.43
O.C. Remon. Tag & Nail in E side 24" Maple	Az. 150°	65.53
O.C. Remon. Tag & Nail in N side 20" White Pine	Az. 260°	95.75
O.C. Remon. Tag & Nail in S side 14" Red Pine	Az. 290°	82.52

Signed by Thomas E. Joiner Date 11-28-94
 Surveyor's Michigan License No. 18435

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983