

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 16W	L-13 S 1/2 corner Section 36 Grand Haven Twp
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:46

D. J. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, THOMAS E. JOINER, in a field survey on 11-7-95, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
05-09-1832 Liber 3 Pg. 376 07-27-79
Post set by Calvin Britain D.S. Set midway and on line
N. 60° W 17 4" Hemlock Between the Southeast
N. 75° E 31 10" Beach and Southwest standard
corners of Section 36
Being on the South
Line of the Township

Liber 3 Pg. 376 07-27-79
Set cast iron monument
SE. 69.15 10" Red Pine
SSW. 63.95 10" Red Pine
NW. 52.58 8" Jack Pine
NE. 65.16 8" Jack Pine

(cont. on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 6, Page 139
West 16.15 to Port Sheldon corner
WNW 61.68 to PK nail East side 6" Oak
SE 91.14 to Nail NE side 12" Pine

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11-20-95

K. D. Hedewell
YON

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in NE side	7" Red Oak	AZ. 323°	61.62
O.C. Remon Tag & Nail In E side	8" Jack Pine	AZ. 0°	32.04
O.C. Remon Tag & Nail in W side	10" Red Pine	AZ. 149°	41.18
O.C. Remon Tag & Nail in NE side	13" Red Pine	AZ. 125°	64.40



Signed by

Thomas E. Joiner
18435

Date

11-16-95

Surveyor's Michigan License No.

A. cont.

Liber 6 Page 139
LCRC Liber 3 Page 394 1979
Roon set 3/4" pipe 10' from
Port Sheldon corner $\frac{1}{2}$ ± of
Job between corners at West
side of Section

Liber 6 Page 139
Found Cast Iron Monument
West 16.15 to Port Sheldon corner
West 6.26 to $\frac{1}{2}$ " Rerod Liber 3 Page 394
NE 56.10 to Nail NW side 10" Pine
WNW 61.68 to PK nail East side 6" Oak
NW 31.76 to nail & cap West side 10" Pine
SE 91.14 to nail NE side 12" Pine

\$ 11.00 CORNER