

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In:	Corner Code-#
1. Public Land Survey	T 7N R 16W	M-2, E 1/4 corner Section 1 Grand Haven Twp
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

95 NOV 29 PM 1:39

Polina Carlson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, THOMAS E. JOINER, in a field survey on 11-2, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

06-16-1832	Liber 2, Page 91 03-23-73	Liber 1, Page 827 01-09-73
Post Set By Calvin Britain, D.S.	Found T-Iron In Monument Box	Found Iron In Monument Box
N 19° W 6 10" Pine	SW 46.63 26" Oak	SW 47.70 18" Oak
S 58° W 19 18" Pine	NE 46.03 Telephone Pole	NW 39.05 Telephone Pole
	WNW 103.53 36" Twin Oak	NE 46.4 Telephone Pole

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" Iron and Accepted as a careful and faithful perpetuation of the position of the original corner. Set Cast Iron Monument.

Liber 2, Page 91 03-23-73	Liber 1, Page 827 01-9-73
NE 46.03 Telephone Pole	SW 47.7 18" Oak
WNW 103.53 36" Twin Oak	NW 39.05 Telephone Pole

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Richard D. Newell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in N side of 40" Oak	AZ 75°	115.20
O.C. Remon Tag & Nail in NE side of 14" Maple	AZ 149°	72.37
O.C. Remon Tag & Nail in S side of Twin 26" Oak	AZ 288°	105.67
GL Top Operating Bolt Hydrant	AZ 304°	49.78



Signed by Thomas E. Joiner Date 11-16-95
Surveyor's Michigan License No. 18435