

**SURVEY & REMONUMENTATION**

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:47

*Richard Kellman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located in: Grand Haven Twp.	Corner Code #: M-6
1. Public Land Survey	T <u>7N</u> R <u>16W</u>	<u>E 1/4 Corner</u> <u>Section 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Englert, in a field survey on October, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-6 E 1/4 corner Section 13  
Original Gov't corner Set May, 1832  
by Calvin Britain D.S.

LCRC Liber 4, Page 313  
Found Iron Pipe from Old Ties  
M-6 Set Cast Iron Monument  
16" Ash NW 59.59  
10" Maple WNW 49.90  
19" Maple NE 62.62  
Robinson Cor. NORTH 41.61

Set 1/2 mile post  
Beech 10" S86°W 22 Links  
Black Ash 12" N80°W 20 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 E 1/4 corner Section 13  
Found 3" Harrison Cast Iron Monument  
Found 19" Maple NE 62.62'  
Found Robinson Corner N. 41.59'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Richard P. Nedewald*

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 E 1/4 corner Section 13  
Set 3/4" x 1.2' long Iron bar with Remon. Cap in Mon. Box on top of X-culvert 3'+/- of road E  
O.C. Remon. Tag & Nail in S. side 7" Maple N81°W 46.51'  
O.C. Remon. Tag & Nail in N.E. side 17" Maple N29°W 58.29'  
O.C. Remon. Tag & Nail in N. side 24" Maple N49°E 63.13'  
O.C. Remon. Tag & Nail in S. side 8" Tw. Maple S80°E 35.46'  
O.C. Remon. Tag & Nail in S.E. side 7" Ash S39°W 46.93'  
T7N, R15W corner NORTH 41.59'

Signed by Carl P. Englert  
Surveyor's Michigan License No. 18987

Date 12/11/94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 1974

