

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:42

Phyllis Coleman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

OTTAWA

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------------|
| 1. Public Land Survey | T <u>7N</u> R <u>16W</u> | M-11, SE Corner |
| | T _____ R _____ | Section 25 |
| | T _____ R _____ | Grand Haven Twp. |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, THOMAS E. JOINER in a field survey on 10-28- 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

05-16-1832	Liber 4, Pg. 57, 05-15-80
Post set by Calvin Britain, D.S.	Set cast in iron monument
S78°W 40 10" Tamarack	SW 28.50 Street Sign
N43°W 35 6" Tamarack	SW 59.82 6" Aspen
	NW 68.75 6" Aspen
	NE 29.90 <u>C_L</u> E. end 24" conc. culvert
	N. 19.13 Robinson corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 4, Pg. 57, 05-15-80
SW 59.82 6" Aspen
NE 29.90 C_L E end 24" concrete culvert
N 19.13 Robinson corner

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Maday D. Nedewell



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon. Tag & Nail SE side 30" Poplar	Az.	255°	82.62
O.C. Remon. Tag & Nail E side 10" Aspen	Az.	205°	68.80
Cut Cross <u>C_L</u> top E end 24" conc. culvert	Az.	20°	29.85
Cut Cross <u>C_L</u> top S end 48" conc. culvert	Az.	135°	32.55
Cast Iron Monument, Robinson Twp. corner, A-11	Az.	0°	19.15

Signed by Thomas E. Joiner Date 11-28-94
Surveyor's Michigan License No. 18435

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983