

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>16W</u>	M-12, E $\frac{1}{2}$ corner Section 36 Grand Haven Twp
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

95 NOV 29 PM 1:39

Elizabeth A. Adelman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, THOMAS E. JOINER in a field survey on 11-2-, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

05-09-1832	Liber 3, Page 394	Liber 4, Page 57
Post Set By Calvin Britain D.S.	Found 1 $\frac{1}{4}$ " Pipe & Brick	Found 2" Well Point
N 40° W 22 10" Beech	NE 57.72 8" Birch	Set Cast Iron Monument
S 55° W 20 10" Hemlock	E 23.55 6" Maple	NE 57.75 10" Birch
	SE 34.18 6" Poplar	W 36.40 20" Oak
		NE 54.65 10" Pepperidge
		E 23.50 8" Maple
		N 9.70 Robinson Corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Liber 4, Page 57
NE 57.75 10" Birch
E 23.50 8" Maple
N 9.70 Robinson Corner

RA. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95
Kendry D. Hedewell
YDM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Cast Iron Monument

O.C. Remon Tag & Nail in N Side 12" Maple	AZ.	87°	23.38
O.C. Remon Tag & Nail in S Side 12" Pepperidge	AZ.	44°	55.03
O.C. Remon Tag & Nail in S Side 30" Oak	AZ.	287°	36.91
O.C. Remon Tag & Nail in NW Side 15" Poplar	AZ.	203°	43.20



Signed by Thomas E. Joiner Date 11-16-95
Surveyor's Michigan License No. 18435