

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**RECORDED**

96 DEC 18 PM 4: 56

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	A-4 (W $\frac{1}{4}$ , 7) Wright Twp.
	T _____ R _____	Common corner to M-4 Polkton Twp.
2. Property Controlling in Section	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	

*Deborah Anderson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on December 6, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
A-4  $\frac{1}{4}$  corner common to Section 7, Wright Twp. and Section 12, Polkton Twp.  
Original Government Corner Record:  
Set qr sec post from which  
a Beech 9 in dia bears S11W 32 lks dist  
& an Ironwood 6 " " " N6W 11 " "  
Post  
John Mullett, Deputy Surveyor  
April 7, 1837

(SEE REVERSE)

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12-9-96  
*D.W.S.*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-4 Found 5/8" x 18" Steel Bar 14" below road surface, cemented in 3" Clay Tile cemented in 8" thick concrete road under Railroad Spike in 4" asphalt surface, and accepted Steel Bar as a careful and faithful perpetuation of the position of the original corner.  
Railroad Spike was 0.15' North and 0.06' West of Steel Bar  
Found spike in SW side of 3" Triple Thornapple N48°E 56.71'(E)  
Found spike in South side of Power Pole S87°30'E 27.99'(E)  
Found spike in NE side of 8" Elm S64°E 39.57'(E)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-4 Removed 5/8" x 18" Steel Bar and Railroad Spike, and replaced Steel Bar with 3/4" x 24" Steel Bar with Ottawa County Remon Cap, 3" below asphalt surface in Monument Box.  
Set Ottawa County Remon Tag & nail in NW side of 4" Quad Apple N47°E 57.91'(E)  
Set Ottawa County Remon Tag & nail in North side of Power Pole S87°30'E 28.00'(E)  
Set Ottawa County Remon Tag & nail in SW side of 8" Elm S64°E 39.49'(E)  
Set Ottawa County Remon Tag & nail in North side of Power Pole S90°W 155.10'(E)  
Centerline asphalt road North & South, 0.4' East  
On centerline fence line East  
On centerline occupation line West  
(SEE SKETCH ON REVERSE)

Signed by Donald W. Schiele Date December 8, 1996  
Surveyor's Michigan License No. 23517

Part A., continued:

From Ottawa County Surveyor records:

(no date): Found Stone: W. 33 to Fence Post

(no date): Found Stone W. 29.5 S. 2' to F. Post

(no date): Iron & Stone NW 43.0 Conc. F. Post  
SW 47.7 C/L 16" Cherry

Approx. 1920: Found Stone & Iron Rod. Placed 3" Tile over Rod in 9' Conc. Rd.

Field notes, 9-22-86, Carl P. Englert: Clay Tile in Conc. Rd.

L. 8 Certified Survey Maps of Ottawa County, P. 647, 4-18-96, Maurice Rosema:

W. 1/4 cor. Sec. 7, T8N, R13W

RR Spk.

Mag nail in S side P.P.	E	28.07'
Spk in N side 6" Cherry	SE	39.57'
Spk in S side 4" Thornapple Clump	NE	56.93'
C/L base of Tele. Box	W	34.94'

