

**SURVEY &  
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**COMMISSION**

For corners in  
Ottawa  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T8N R13W  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

A-10  
W 1/4 cor. Sec.  
30, Wright Twp.  
Common cor  
w/ M-10  
Polkton Twp.

**RECORDED**

95 NOV 29 PM 1:35

*Polkton*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Steven Lampen, in a field survey on November 15 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

A-10	A-10
Old JK & A notes show iron pipe found (1969)	L 7 Certified Surveys P 243 shows cast iron monument
SW cor. concrete guard rail post NW 20.77'	Guard rail post SE 23.24'
SE cor. concrete guard rail post NE 20.77'	"X" in concrete bridge rail NE 18.46'
	"X" in concrete bridge rail NW 18.68'
	Guard rail post SW 23.27'
	LCRC L 5-P 144
	June 27, 1984
	Found R.R. spike, set cast iron mon.
	Guard rail post SE 23.21'
	"X" in concrete bridge rail NE 18.42'
	"X" in concrete bridge rail NW 18.67'
	Guard rail post SW 23.26'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-10  
Found cast iron monument from previous ties. This position not established by original government surveyors. this monument is accepted as the best available evidence of the position of the corner.

Guard rail post	SE 23.24'
"X" in concrete bridge rail	NE 18.46'
"X" in concrete bridge rail	NW 18.68'
Guard rail post	SW 23.27'

PEER APPROVED 11/20/95

*Kevin D. McDowell*  
SDT

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-10  
Cast iron monument

Set O. C. Remonumentation tag & nail in top of guard rail post	S 46° W 23.39'
Set O. C. Remon. tag & nail in top of guard rail post	S 39° E 23.29'
Cut "X" in concrete bridge rail	N 55° E 20.20'
Cut "X" in concrete bridge rail	N 45° W 18.68'



Signed by Steven Lampen

Date November 17, 1995

Surveyor's Michigan License No. 37279