

FEB 24 2000

RECORDED

99 OCT -8 PM 2:19

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Sam [Signature]*

REGISTER OF DEEDS  
OTTAWA COUNTY, MI

SECTION

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 13W	B-11 (N $\frac{1}{4}$ , 31)
	T ___ R ___	Wright Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Donald W. Schiele, in a field survey on Sept. 13, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11	●											
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-11 1/4 corner common to Sections 30 & 31, Wright Twp.  
 Original Government Corner Record: L.C.R.C. recorded in L.5, P.196, 1-25-85 by Gordon D. Nederveld:  
 Beech 10 for qr sec corner B-11 Fd. 3/4" Iron in Mon. Box  
 10" Beech PK Nail in W side T. Pole N 0°E 37.98'  
 (no other ties taken) NE cor. block hse. Fndn. S12°E 67.03'  
 Enoch Hammele, Deputy Surveyor, for NW cor. Block Hse. Fndn. S12°W 66.67'  
 Rasselas Whitcomb, Deputy Surveyor  
 Between 9-18 & 9-26, 1838

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Found 3/4" X 11" Iron Pipe in Monument Box, 7" below surface of asphalt road, and accepted as a careful and faithful perpetuation of the position of the original corner.  
 Found nail in West side of cut-off Telephone Pole N00°30'E 37.80'(E)  
 NE corner, house foundation S12°E 67.01'(E)  
 NW corner, house foundation S12°30'W 66.62'(E)  
 Found nail in West side of Power Pole S32°W 62.67'(E)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 Removed 3/4" X 11" Iron Pipe, and replaced with 3/4" X 24" Steel Bar with Ottawa County Remon Cap, 1 1/2" below surface of asphalt road in Monument Box.  
 Set Ottawa County Remon Tag & nail in West side of cut-off Telephone Pole N00°30'E 37.81'(E)  
 Top of NE corner, cyclone fence S73°30'E 105.86'  
 NE corner, house foundation S12°E 67.01'(E)  
 NW corner, house foundation S12°30'W 66.62'(E)  
 Set Ottawa County Remon Tag & nail in West side of Power Pole S32°W 62.67'(E)  
 Centerline East & West asphalt road, 0.5' North  
 Field line to North, 6'± West.

9/20/99

*[Signature]*

Signed by Donald W. Schiele  
Surveyor's Michigan License No. 23517

Date September 13, 1999

