

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

96 DEC 18 PM 4: 56

For corners in

<u>Ottawa</u> <small>(County)</small>	Located in:	Corner Code \neq
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>D-1 (N$\frac{1}{4}$, 5)</u> <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Richard Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on December 9, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-1 North $\frac{1}{4}$ corner, Section 5, Wright Township.

Original Government Survey by
Enoch Hammele, Deputy Surveyor, for
Russelas Whitcomb, Deputy Surveyor
between 9-18 and 9-26, 1838.
Corner not set.

(SEE REVERSE)

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96
J.D.M.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found broken Cast Iron Monument, 6" below surface of gravel road.
Found Cast Iron Monument, S. $\frac{1}{4}$ cor., Sec. 32, T9N, R13W S90°W 70.16'(E)
C/L hole in North end of Corrugated Metal Culvert N59°30'W 28.04'(E)
ENE corner of Metal Wingwall N53°30'W 32.82'(E)
Also found 1 $\frac{1}{2}$ " Iron Pipe, 18" below road surface, 1.92' South of the South line of Sec. 32, T9N, R13W and 8.94' East of the broken Cast Iron Monument.
The position of D-1 not established by original government surveyors.

The broken Cast Iron Monument appears to have been established using improper procedures and is not utilized in this survey. It also appears that the 1 $\frac{1}{2}$ " Iron Pipe was in existence at the time the Cast Iron Monument was placed, and an attempt had been made to establish its position by single proportionate measurement. However, since it falls South of the Township line and East of the true mid-point, it is not utilized in this survey. This corner has been established on the Town line by single proportionate measurement between closing corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Set 3/4" x 24" Steel Bar with Ottawa County Remon Cap, 6" below surface of gravel road.
Set Ottawa County Remon Tag & nail in North side of 22" Walnut S87°30'E 664.43'(E)
1 $\frac{1}{2}$ " Iron Pipe S48°E 2.88'
Set Ottawa County Remon Tag & nail in NW side of 8" Ash S28°30'W 244.12'(E)
Set Ottawa County Remon Tag & nail in SE side of 12" Poplar S73°W 103.99'(E)
Centerline broken Cast Iron Monument S90°W 6.79'
Cast Iron Monument, S. $\frac{1}{4}$ cor., Sec. 32, T9N, R13W S90°W 76.95'(E)
Centerline hole in North end of Corrugated Metal Culvert N65°W 34.07'(E)
Centerline gravel road East & West, 1' South
(SEE SKETCH ON REVERSE)

Signed by Donald W. Schiele Date December 9, 1996
Surveyor's Michigan License No. 23517

