

EDS
COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 15 AM 9:27

Regina Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa
(County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>8N</u>	R	<u>13W</u>	<u>D-5 (N$\frac{1}{4}$, 17)</u>
	T		R		<u>Wright Twp.</u>
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on November 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-5 corner common to Sections 8 & 17, Wright Twp.

L.C.R.C. recorded in Liber 2, Page 729, 1-14-75.

L.C.R.C. recorded in Liber 3, Page 64, 3-29-76

L.C.R.C. recorded in Liber 3, Page 270, 06-12-78

Fd. Stone (Bent Iron over Stone)

C.I.M.
Fence Post NNE 30.05'

C.I.M.
Fence Post N45°W 45.65'

SW Cor. Sec. 8 W 2641.52'

Chiseled Cross on West

Fence Post N42°E 40.23'

FC running North W 163.5'±

End of Concrete

C.L. Rock S13°E 25.7'

FC Post NNE 30.05'

Driveway Culvert SE 27.15'

Fence N West 284'±

Chiseled cross on W-End Conc. Culv. SE 27.15'

SW Cor. Sec. 8 is W. 2641.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found Cast Iron Monument with top broken off and accepted as a careful and faithful perpetuation of the position of the original corner.

Found PK nail in West side of Power Pole N18°E 223.32'(E)

Found PK nail in East side of Power Pole N18°E 223.37'(E)

Found chiseled cross on West end of Concrete Culvert SSE 27.08'

NW Corner, Section 17 West 2641.05'(E)

Centerline of Rock S13°E 24.7'

Found PK nail in NE side of Power Pole N52°W 337.70'(E)

Centerline Fence to North West 264'±

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 Cast Iron Monument with top broken off 4" below surface.

Set Ottawa County Remon Tag & nail in East side of Power Pole N18°E 223.37'(E)

Set Ottawa County Remon Tag & nail in North side of 8" Elm S85°E 280.17'(E)

Cross chiseled on West end of 10" Concrete Culvert S45°E 27.08'

Set Ottawa County Remon Tag & nail in South side of Fence Post N81°W 267.04'(E)

Set Ottawa County Remon Tag & nail in SW side of Power Pole N52°W 337.66'(E)

On Centerline gravel road East & West

Signed by

Donald W. Schiele

Date

Dec. 6, 1993

Surveyor's Michigan License No.

23517

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 31, 1975
REVISED JAN., 1983

