

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

**RECORDED
96 DEC 18 PM 4:55**

Donald W. Schiele
**REGISTER OF DEEDS
OTTAWA COUNTY, MI**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	E-1 (NE, 5) <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald W. Schiele, in a field survey on December 5, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1 NE corner, Section 5, Wright Twp.	L.C.R.C. recorded in Liber 3, Page 66, 3-29-76:
Original Government Corner Record:	E-1
Set post cor to Secs 4 and 5	Set cast iron Mon.
Post (Standard corner 1.25 W.)	12" quad boxelder SE 35.85'
Ironwood 5 S60W 25	16" Maple SW 30.55'
Beech 12 S20E 24	Tel. pole NW 54.44'
Enoch Hammele, Deputy Surveyor, for	Chester cor. W. 88.50'
Rasselas Whitcomb, Deputy Surveyor	
Between 9-18 and 9-26, 1838	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 Found Cast Iron Monument inscribed "Section Corner", 4" below asphalt surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found Cast Iron Monument, SE cor., Sec. 32, T9N, R13W	S90°W	88.52' (E)
Found nail in NE side of Telephone Pole	N49°W	54.32' (E)

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96

G.D.N.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Established amended corner at intersection of the East line of Sec. 5 with the S. line of Sec. 33, T9N, R13W, which point falls on top of the existing Cast Iron Monument.

Centerline, Cast Iron Monument	North	0.07'
Set Ottawa County Remon Tag & nail in SE side of Power Pole	N39°30'E	133.99' (E)
Set Ottawa County Remon Tag & nail in NE side of 12" Ironwood	S55°30'E	65.85' (E)
Set Ottawa County Remon Tag & nail in East side of 16" Oak	S06°30'E	50.55' (E)
Cast Iron Monument, SE cor., Sec. 32, T9N, R13W	S90°W	88.52' (E)
Set Ottawa County Remon Tag & nail in NE side of Telephone Pole	N49°W	54.28' (E)

On occupation line to South, ±
On centerline asphalt road East & West
(SEE SKETCH ON REVERSE)

Signed by Donald W. Schiele Date December 7, 1996

Surveyor's Michigan License No. 23517

