

DEC 01 1993

93 NOV 11 AM 11:55

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Donald W. Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa
(County)

Located In: Corner Code #

1. Public Land Survey	T 8N R 13W	E-6 (E $\frac{1}{4}$, 17)
	T _____ R _____	Wright Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6 corner common to Sections 16 & 17, Wright Twp. L.C.R.C. recorded in Liber 1, Page 393, 5-11-72 C.I.M.	West 75.62'	C.I.M.		
Nail in Face of 16" Ash	NE 31.53'	30" Maple	N12°E	120.65'
Nail in Face of Twin 12" Oak	NE 79.01'	12" Spruce	N22°E	79.00'
Nail in Face of 8" Blue Spruce	NE 70.91	NW Cor. Hse.	N29°E	90.18'
SW Cor. Hse. # 17206	NE 90.08	20" Twin Oak	N58°E	32.71'
NW Cor. Hse. # 17206				

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found Cast Iron Monument with top broken off and accepted as a careful and faithful perpetuation of the position of the original corner.

Reading in West side of 46" Maple	N10°E	120.68'
Reading in South side of 18" Spruce	N23°E	78.82'
NW Corner Foundation to House # 17206	N32°E	90.10'
SW Corner Foundation to House # 17206	N50°E	70.92'
Reading in SE side of 24" Twin Oak	N65°E	32.69'
Face of 28" Ash	N86°W	75.3'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Cast Iron Monument with top broken off 3" below surface.


NW Corner Foundation to House # 17206	N32°E	90.10'
Sw Corner Foundation to House # 17206	N50°E	70.92'
Set Ottawa County Remon Tag & nail in SE side of 24" Twin Oak	N65°E	32.66'
Set Ottawa County Remon Tag & nail in SE side of 11" Maple	S29°W	60.27'
Set Ottawa County Remon Tag & nail in South side of 28" Ash	N86°W	76.20'

On Centerline gravel road North and South

Signed by Donald W. Schiele

Date Nov 8, 1993

Surveyor's Michigan License No. 23517



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED JAN., 1975
REVISED JAN., 1983