

**SURVEY & REMONUMENTATION**

APR 05 1996

**COMMISSION** OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa	Located In:	Corner Code #
(County)	Wright Twp	
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	E-10
	T ___ R ___	W- $\frac{1}{4}$ Corner
	T ___ R ___	Section 28
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

**RECORDED**  
 95 NOV 29 PM 1:41  
*Deborah R. Robinson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Carl P. Englert, Jr., in a field survey on October 31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 E-10  
 1/4 corner common to Sections 28 & 29  
 Original corner set September, 1838 by Enock Hammele  
 Set  $\frac{1}{4}$  Section Post  
 Sugar 12" N. 60° W. 17 Links  
 Beech 8" S. 15° E 13 Links

LCRC Liber 4, Page 248 10/22/1981  
 Found  $\frac{1}{2}$ " Iron, Set Cast Iron Mon.  
 6" Ash West 27.15'  
 7" Apple West 52.40'  
 6" Apple SE 76.20'  
 Occupation lines E & W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10  
 1/4 corner common to Sections 28 & 29  
 Found 4" CIM in CL Gravel Road on occupation E & W  
 Found 12" Apple SE 76.20'

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 11/20/95


*Madog P. Madwell*  
 207

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10  
 1/4 corner common to Sections 28 & 29  
 4" CIM in CL Gravel Road  
 Ottawa County Remonumentation Tag and Nail in S. Side P.P. N 65° W 198.35'  
 Ottawa County Remonumentation Tag and Nail in S. Side 8" Ash S.65° W 74.94'  
 Ottawa County Remonumentation Tag and Nail in W. Side 6" Ash N 06° E 166.46'  
 Ottawa County Remonumentation Tag and Nail in S. Side 4" Apple N 88° E 44.68'

Signed by Carl P. Englert Jr.  
 Surveyor's Michigan License No. 18987



Date 11/10/1995