

**SURVEY & REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**RECORDED**  
94 DEC 15 AM 11:47

For corners **COMMISSION**

*Elizabeth Kullman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code --#
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>E-12 (W/4, 33)</u> <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
E-12 1/4 corner common to Sections 32 & 33, Wright Twp.  
Original Government L.C.R.C. recorded in Liber 3, Page 46, 3-29-76  
Corner Record: Set qr sec post  
Set qr sec post between Sec. 32 & 33  
Post Triple 16" poplar SE 133.77'  
P. pole ENE 148.52'

L.C.R.C. recorded in Liber 6, Page 26, 1-3-90 Found Iron PK in S side PP  
N71°36'E 146.55'  
SW cor Br. Hse  
N23°17'E 250.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
E-12 Found Cast Iron Monument inscribed "Section Corner", 1 1/2" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.  
SW corner, brick face to House # 14846 N23°17'E 250.75'(E)  
Found PK nail in South side of Power Pole N71°30'E 148.47'(E)  
Found nail in South side of Power Pole N71°30'E 148.37'(E)

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

*Robert D. Medved*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-12 Cast Iron Monument inscribed "Section Corner", 1 1/2" below surface.  
SW corner, brick face to House # 14846 N23°17'E 250.75'(E)  
Set Ottawa County Remon Tag & nail in South side of Power Pole N71°30'E 148.39'(E)  
Set Ottawa County Remon Tag & nail in West side of Power Pole S25°E 361.86'(E)  
Set Ottawa County Remon Tag & nail in East side of Power Pole S20°W 361.83'(E)  
Centerline asphalt road North & South, 0.4' West  
Field line to West, 33'± South

Signed by Donald W. Schiele Date DEC. 12, 1994  
Surveyor's Michigan License No. 23517