

# SURVEY & REMONUMENTATION

APR 24 1995

## OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:47

For corners in **COMMISSION**

*Richard R. Hartman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	E-13 (SW, 33)	
	T _____ R _____	Wright Twp.	
	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-13 SE corner of Section 32 & SW corner of Section 33, Wright Twp.		
Original Government Corner Record:	L.C.R.C. recorded in Liber 3, Page 46, 3-29-76	L.C.R.C. recorded in Liber 6, Page 26, 1-3-90
Set corner post of Sec. 32 & 33	Set cast iron Mon.	Set CIM
Post	Tel. pole SW 32.65'	SE cor Hse NW 131.13'
Beech 10 N37W 32	C/L St. Sign WSW 55.12'	NW cor 3x3' conc pad for MBT box SW 47.54'
Do 12 N19E 24	8" Cherry NE 86.34'	SW cor Hse NE 144.08'
Noah Brookfield, Deputy Surveyor	14" Pine NNW 88.95'	
April 12, 1837		

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-13 Found Cast Iron Monument inscribed "Section Corner", 3" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.

SW frame corner to House # 14428	N32°30'E	144.13' (E)
Centerline 16" Cherry	N52°30'E	86.3'
Found nail in NW side of Telephone Pole	S39°30'W	32.36'
SE corner, foundation to House # 3211	N36°30'W	131.11' (E)
Found PK nail in West side of 22" Pine	N19°30'W	88.71'
Found nail & Tag # 14091 in West side of 22" Pine	N19°30'W	88.75'



RA. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94  
*Richard D. Hedrick*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-13 Cast Iron Monument inscribed "Section Corner", 3" below surface in Monument Box.

SW Frame corner to House # 14428	N32°30'E	144.13' (E)
Set Ottawa County Remon Tag & nail in NE side of 10" Elm	S58°30'E	73.69'
Set Ottawa County Remon Tag & nail in NW side of Telephone Pole	S39°30'W	32.37'
Cast Iron Monument	N88°W	159.42'
SE corner, foundation to House # 3211	N36°30'W	131.11' (E)
Set Ottawa County Remon Tag & nail in East side of 22" Pine	N19°30'W	88.51'
On centerline asphalt roads North, East & West		

Signed by Donald W. Schiele Date Dec. 12, 1994  
Surveyor's Michigan License No. 23517