

**SURVEY & REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:46

For corners **COMMISSION**

*Deborah R. Balthasar*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	F-13 (S $\frac{1}{4}$ , 33) Wright Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-13 South  $\frac{1}{4}$  corner, Section 33, Wright Twp.  
Original Government L.C.R.C. recorded in Liber 3, L.C.R.C. recorded in Liber 6,  
Corner Record: Page 46, 3-29-76 Page 24, 1-3-90  
Set qr sec post on Set cast iron Mon. Set CIM  
South side Sec. 33 Fence cor. N 24.80' N $\frac{1}{4}$  cor 4-7-13 W 192.09'  
Post Tailmadge corner W 192.69' PK in Fence Post N 33.78'  
Beech 12 N65E 28 Nail in PP SW 230.83'  
Do 10 N68W 30 Nail in PP SE 223.95'  
Noah Brookfield, Deputy Surveyor PK in Fence Post NW 51.53'  
April 12, 1837

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found Cast Iron Monument inscribed "Section Corner", 3" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.  
Found nail in North side of Power Pole S42°W 230.88' (E)  
Cast Iron Monument N89°30'W 192.12' (E)  
Found PK nail in East side of Fence Post N50°W 51.33'  
Found PK nail in East side of corner Fence Post N01°W 33.75'  
Found Capped Iron # 16048 N01°W 32.95'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED *[Signature]*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Cast Iron Monument inscribed "Section Corner", 3" below surface in Monument Box.  
SW corner, porch foundation to House # 2775 N58°E 187.63' (E)  
Set Ottawa County Remon Tag & nail in NE side of Power Pole S40°30'E 223.62' (E)  
Set Ottawa County Remon Tag & nail in SE side of Power Pole S42°W 230.98' (E)  
Cast Iron Monument N89°30'W 192.12' (E)  
Set Ottawa County Remon Tag & nail in East side of corner Fence Post N01°W 33.70'  
On fence line to North  
Centerline asphalt road East & West, 0.4' North

Signed by Donald W. Schiele Date DEC 12, 1994  
Surveyor's Michigan License No. 23517