

**SURVEY &
REMONUMENTATION**

APR 05 1996 OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

Located In:	Corner Code #
Wright Twp	G-10
T 8N R 13W	E 1/4 Corner
T R	Section 28
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling
in Section

3. Miscellaneous
Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECORDED

95 DEC 12 AM 11:51

Robert Chalmers
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Carl P. Englert, Jr., in a field survey on October 31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-10 1/4 Corner common to Sections 27 and 28
 Original Corner set September 1838
 by Enock Hammele
 Set 1/4 Section Post
 Beech 8" N 20° W 16 Links
 Sugar 15" S 15° W 32 Links

LCRC Liber 3, Page 48
 Found "T" Iron, set Cast Iron Monument
 Plat Mon. West 33.00'
 Plat Mon. East 33.00'
 T.P. E. 41.41'
 P.P. ESE 61.44'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 1/4 Corner common to Sections 27 & 28
 Found Capped Iron set 3/4" 2' Long Steel Bar with Ottawa County Remonumentation Cap in road CL
 Found PK in N. Side P.P. WNW 61.74'
 Found PK in N. Side P.P. W. 41.56'
 Conc. Mon, E. 33.00'
 Nail in Ely Side 10" W. Cherry SSW 98.97'

PA. 345 OTTAWA COUNTY
 PEER APPROVED 11/20/95
Robert D. Redwood

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 1/4 Corner common to Sections 27 & 28
 3/4" X 2' Long Steel bar with Ottawa County Remonumentation cap and placed Mon Box
 Ottawa County Remonumentation tag and nail in S.W. side 6" Ash S. 51° E 73.66'
 Ottawa County Remonumentation tag and nail in W. side 18" Aspen N. 26° E 145.45'
 Ottawa County Remonumentation tag and nail in N.E. side 10" Tw Maple N 33° W 120.41'
 Ottawa County Remonumentation tag and nail in N. side P.P. N. 89° W. 41.55'
 Ottawa County Remonumentation tag and nail in 12" Cherry S. 20° W. 98.83'
 CL Asphalt pavement West 0.2'±

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 118987

Date 11/13/1995



G-10 T8N, R13W
LCRC Liber 6, Page 64 10/15/90
Set corner 33.00 feet W of Existing Mon.
at the SW corner of Little Farms Plat No. 1
Set corner on line with the East 1/4 corner
of Section 27.
Set capped ReRod
CL N-S B.T. Road W. 0.2'±
PK in N. Side P.P. W. 41.56'
PK in N. Side P.P. WNW 61.74'
Conc Mon E. 33.00'
Nail in Ely Side 10" W. Cherry SSW 98.97'

\$ 11.00
CORNER