

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:39

Polystis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

corners in **COMMISSION**

Ottawa (County)	Located In:	Corner Code #
Public Land Survey	T <u>8N</u> R <u>13W</u>	G-11 (NE, 33) Wright Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Donald W. Schiele, in a field survey on October 17, 1994,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
-11 corner common to Sections 27, 28, 33 & 34, Wright Twp.
Original Government Corner Record: L.C.R.C. recorded in Liber 3, Page 48, 3-29-76
Set corner post Sec. 27, 28, 33, 34. Set cast iron Mon.
Post 18" Hickory ENE 51.0'
No ties taken) P. Pole WNW 90.50'
Loch Hammele, Deputy Surveyor C/L concrete R/W marker WSW 67.80'
between 9-18 and 9-26, 1838

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
-11 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 3" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found PK nail in North side of 22" Hickory	N80°30'E	50.47'
Found concrete nail in NE side of 25" Maple	S45°30'E	134.45'
Centerline Concrete Right-of-Way marker	S61°30'W	67.73'
Found PK nail in SE side of Telephone Pole	S65°W	69.66'
Found PK nail in SW side of Telephone Pole	N31°W	92.35'
Found nail in face of Telephone Pole	N31°W	91.93'



Description of monument for corner and accessories established to perpetuate locating the position of the corner:
-11 Cast Iron Monument inscribed "Ottawa County Section Corner", 3" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in North side of 22" Hickory	N80°30'E	50.51'
Set Ottawa County Remon Tag & nail in NE side of 25" Maple	S45°30'E	134.47'
Centerline Concrete Right-of-Way marker	S61°30'W	67.73'
Set Ottawa County Remon Tag & nail in South side of Power Pole	N69°30'W	91.60'
Set Ottawa County Remon Tag & nail in NE side of Telephone Pole	N31°W	92.47'
Centerline asphalt road North & South		
Centerline gravel road West, 2' North		

PA. 345 OTTAWA COUNTY

PEER APPROVED 10/17/94

Surveyed by Donald W. Schiele Date Oct. 17, 1994
Surveyor's Michigan License No. 23517