

RECORDED

99 OCT -8 PM 2:19

FEB 24 2000

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sam Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

SECTION

For corners in

<u>Ottawa</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 8N R13W	I-2 (W/2)
	T R	Wright Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald W. Schiele, in a field survey on Sept. 13 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2 1/4 corner common to Sections 2 & 3, Wright Twp.
 Original Government Corner Record: L.C.R.C. recorded in L.2, P.631, 10-9-74 by C.P.Englert:
 Set qr Sec post I-2 (Found) Stone & plow point
 Post Set 5/8" rod under stone
 Lynn 48 S88E. 12 N.E. 25.74 30" Beech
 Beech 15 N57W. 20 N.W. 26.03 30" Beech
 Enoch Hammele, Deputy Surveyor, for W. 47.82 10" Ash
 Rasselas Whitcomb, Deputy Surveyor E. 37.70 10" Maple
 Between 9-18 and 9-26, 1838

L.C.R.C. recorded in L.4, P.234, 10-22-81 by Thomas E. Joiner:
 I-2 Set Cast Iron Monument
 30" Beech NE 25.74
 30" Beech NW 26.03
 10" Ash West 47.82
 10" Maple East 37.70

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2 Found Cast Iron Monument (broken), 3" below ground level on North edge of small ditch, and accepted as a careful and faithful perpetuation of the position of the original corner.
 Found nail in SW root of 26" Beech N55°30'E 25.67'(E)
 Found nail in South side of 16" Ash S88°W 47.73'(E)
 Found nail in East root of 28" Beech N42°30'W 25.90'(E)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 Broken Cast Iron Monument, 3" below ground level on North edge of small ditch.
 Set Ottawa County Remon Tag & nail in NW side of 26" Beech N55°30'E 26.87'(E)
 Set Ottawa County Remon Tag & nail in South side of 14" Maple N87°30'E 37.60'(E)
 Set Ottawa County Remon Tag & nail in South side of 16" Ash S88°W 47.74'(E)
 Set Ottawa County Remon Tag & nail in SW side of 6" Elm N44°30'W 14.65'(E)
 On fence line (remnants) ±, East & West

\$9.00 CORNER
Receipt #39918

Signed by Donald W. Schiele
 Surveyor's Michigan License No. 23517



Date September 13, 1999