

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 OTTAWA COUNTY REMONUMENTATION
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in: Wright Twp.
 Located in: OTTAWA (County)
 Corner Code # I-10

1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>E 1/4</u> Corner
	T ___ R ___	<u>Section 27</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
 95 NOV 29 PM 1:41
Elizabeth Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Carl P. Englert, Jr., in a field survey on October 31, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-10 1/4 Corner common to Sections 26 & 27
 Original Corner set September, 1838
 by Enoch Hammele
 Set 1/4 Section post
 Sugar 12" N 37° E 20 Links'
 Beech 10" S 22° E 18 Links'

LCRC Liber 1, Page 199, 4/10/1971
 Found 1/2" iron in Mon. Box
 Fe Post E 32.82'
 24" Walnut N 27° E 57.35'
 20" Oak N 42° W 48.50'
 MBT Pole N 85° W 50.60'
 CL B.T. Road W. 3.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 1/4 Corner common to Sections 26 & 27
 Found 3/4" iron in Mon. Box & Set 3/4" X 2' Long Steel Bar & Remonumentation Cap in Mon Box
 Found Fe Post E 33'± (Leaning)
 Found 30" Walnut N 27° E 57.35'
 Found 30" Oak N 42° W 48.50'
 MBT Pole N 85° W 50.60'


P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11/20/95
Kendry P. Pedwell

Accepted as a faithful and careful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 1/4 Corner common to Sections 26 & 27
 3/4" X 2' Long Steel Bar with Ottawa County Remonumentation Cap in Mon Box
 Ottawa County Remonumentation Tag and Nail in N. side P.P. N 84° W 50.80'
 Ottawa County Remonumentation Tag and Nail in W. side 30" Walnut N 24° E 57.77'
 Ottawa County Remonumentation Tag and Nail in E. side 30" Oak N 39° W 48.18'
 Ottawa County Remonumentation Tag and Nail in N. side 18" Maple N 88° E 53.96'
 Centerline Asphalt Road West 3.2'±

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987



Date 11/10/1995