

SURVEY & REMONUMENTATION

APR 24 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 94 DEC 15 AM 11:53

COMMISSION

For corners in

D. Schiele
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code -#
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>I-13 (SW, 35)</u> <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Donald W. Schiele, in a field survey on December 2, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 SE corner of Section 34 & SW corner of Section 35, Wright Twp.
 Original Government Corner Record: L.C.R.C. recorded in Liber 3, page 262, 3-7-78
 Lynn 18 for cor of Sec. 34 & 35 Found small nail under 2" B.T. by previous
 18" Lynn witnesses.
 (no ties taken) SE Cor. Gar. N25°E 73.5'
 Noah Brookfield, Deputy Surveyor SW Cor. Gar. N52°W 74.9'
 April 12, 1837 Brass Plug 76.6' W. & 0.7' N.

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 5" Nail on centerline of Hayes Street; and accepted as a careful and faithful perpetuation of the position of the original corner.
 SW'ly corner, SE corner Concrete Block Building N27°E 73.42'
 Found PK nail in NE side of Power Pole S62°E 59.00'
 Found PK nail in SW side of Power Pole S62°E 58.83'
 Brass Cap in Monument Box West 77.02'
 SE'ly corner, SW corner Concrete Block Building N30°W 74.88'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

Robert D. Hedgewood

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Removed 5" nail and replaced with 3/4" X 36" Steel Bar with Ottawa County Remon Cap, 2 1/2" below surface in Monument Box.
 SW'ly corner, SE corner Concrete Block Building N27°E 73.42'
 Set Ottawa County Remon Tag & nail in NE side of Power Pole S62°E 58.84'
 Set Ottawa County Remon Tag & nail in NW side of Power Pole S28°W 61.97'
 Brass Cap in Monument Box West 77.02'
 SE'ly corner, SW corner Concrete Block Building N30°W 74.88'
 On centerline asphalt road East & West



Signed by Donald W. Schiele

Date DEC. 12, 1994

Surveyor's Michigan License No. 23517

PART A. continued:

L.C.R.C. recorded in Liber 5, Page 103, 3-20-84
I-13

Found PK nail on centerline of Hayes Street

SE cor. conc. block bldg.	NE	73.42'
SW cor. conc. block bldg.	NNW	74.92'
PK in N'ly side P. Pole	ESE	58.92'
Brass cap in Mon. box (NE cor., Sec. 3)	W	77.00'
Center of cor c/l fence post	SW	43.13'