

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 JUL 24 PM 2:26

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>J-1 (N<math>\frac{1}{4}</math>, 2)</u> <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Phyllis Chittenden*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on June 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

J-1 North  $\frac{1}{4}$  corner, Section 2, Wright Twp. From survey, N. line Sec. 2, 5-24-16, by Original Government survey by E.H. Peck & C. Barnard:  
 Enoch Hammele, Deputy Surveyor, for  
 Rasselas Whitcomb, Deputy Surveyor  
 Between 9-18 and 9-26, 1838  
 Corner not set.  
 Did not find cor.  
 Stone & iron 65' West for Chester Cor.

(SEE REVERSE)

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

J-1 Established corner by single proportionate measurement between the NW corner of Sec. 2 and the NE corner of Sec. 2, on line between the South  $\frac{1}{4}$  corner of Sec. 35, T.9 N., R.13 W., and the SE corner of Sec. 35, T.9 N., R.13 W. Agrees with "T" iron found on the East line of Consumers Power Co. property at the Southerly right-of-way line of Wilson Street.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 7-21-97

*D. W. Schiele*



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J-1 Set 3/4" X 24" steel bar with Ottawa County Remon Cap, 2" below asphalt surface in Monument Box:

Set Ottawa County Remon Tag & nail in NE side of Gate Post	S58°E	45.04' (E)
Set Ottawa County Remon Tag & nail in West side of Gate Post	S14°E	24.14' (E)
Set Ottawa County Remon Tag & nail in SE side of 14" Apple	S27°W	52.39' (E)
Cast Iron Monument in Monument Box, South $\frac{1}{4}$ cor., Sec. 35, T9N, R13W	S90°W	64.66' (E)
Set Ottawa County Remon Tag & nail in NE side of Power Pole	N61°30'W	75.25' (E)

On occupation line to South  $\pm$   
 Centerline asphalt road East & West, 1.70' North  
 (SEE SKETCH ON REVERSE)

\$ 11.00 CORNER

Signed by Donald W. Schiele

Date July 21, 1997

Surveyor's Michigan License No. 23517

Part A., continued:

From Ottawa County Surveyor records, 10-35:

Found Large Stone		
Fence	S	35.4
3" Apple	N	26.3
3" Apple	NE	48.0
3" Apple	NW	50.5

From Williams & Works survey for Consumers Power Co., 1968, by Gordon L. Bonney:

(Field notes indicate "PK" nail set at N. 1/4 cor., Sec. 2. No witnesses taken.)

