

**SURVEY &  
REMONUMENTATION**

APR 05 1996

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In: Wright Twp	Corner Code #
1. Public Land Survey	T 2N R 13W	J-7
	T R	S 1/4 Corner
	T R	section 14
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Englert, Jr., in a field survey on October 31 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-7 1/4 Corner common to Sections 14 & 23  
Original Corner set September, 1838  
by Enock Hammele  
Set 1/4 section Post  
Beech 18" S 61° E 10 Links  
Beech 12" N 20° E 18 Links

LCRC Liber 3, Page 60 1/14/1976  
Found Stone & Bricks,  
Set Cast Iron Monument  
20" Basswood SSE 23'  
16" Ash S. 31.18'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-7 1/4 Corner common to Sections 14 & 23  
Found Cast Iron Monument  
16" Ash (now stump) S. 31.18±

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95


*Richard P. Redwood*  
RDR

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 1/4 corner common to Sections 14 & 23  
4" Cast iron Monument with Broken Top 3" Deep in CL of Gravel Road  
Ottawa County Remonumentation Tag and Nail in SE Side of P.P. S 36° W 32.40'  
Ottawa County Remonumentation Tag and Nail in N. Side P.P. S 86° W 346.56'  
Ottawa County Remonumentation Tag and Nail in S. side Elm Clump N 69° W 92.68'  
Ottawa County Remonumentation Tag and Nail in E. Side P.P. N 4° E 36.20'

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987



11/10/1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995